



## Addendum 2

June 9, 2021

### **RFP R21-16 Asbestos Abatement 1080 Piercy Ave – Addendum No. 2**

---

This addendum forms part of the RFP document and shall be read, interpreted, and coordinated with all other parts. The costs of all work contained herein shall be included in the submission. The following revisions supersede the information contained in the original documents to the extent referenced and shall become part thereof.

#### **Item No. 1 – Clarifications**

---

1. Metallic, non-hazardous materials can be disposed of in the City Public Works metal bin.
2. Drywall behind the electrical panels is to be removed. The City can request a hydro service disconnect if successful Proponents desires.
3. All lighting and baseboard heaters are to be removed and disposed of.
4. The bathroom floor tiles are to remain.
5. Bathroom stalls and hardware are to be removed, but saved for future use by the City.
6. The drywall ceilings in the bathroom and adjacent utility room are to be removed.
7. The suspended ceiling tiles and framework are to be removed and disposed of.

---

**Acknowledgement of this Addendum must be part of your submission.**

**End of Addendum No. 2**

**Graham Peterson  
Procurement Specialist  
City of Courtenay**